

managing risk with responsibility

Jeffrey S. Moquin, Director Risk Management Department

January 18, 2007

Telephone: 754-321-3200 Facsimile: 754-321-3290

Signature on File

TO: Mr. Charles Neely, Principal

Cypress Bay High School

FROM: Robert J. Krickovich, Coordinator, LEA

Facilities and Construction Management, Environmental Division

SUBJECT: Indoor Air Quality (IAQ) Assessment

Portable 1214C

On December 11, 2006 Richard Rosa conducted an assessment of Portable 1214C at Cypress Bay High School. This evaluation included observations of the flooring system, ceiling tiles, false ceiling plenum, environmental surfaces, interior and exterior walls, and the accessible ventilation equipment. Additionally, environmental parameter measurements were taken to include temperature, relative humidity, and carbon dioxide. The detailed findings, along with the recommended corrective action can be found on the attached IAQ Assessment Worksheets.

The IAQ assessment did identify one or more existing conditions impacting IAQ and has generated appropriate work orders to correct deficiencies in systems and maintenance that could contribute to decreased indoor air quality. At the time of the assessment, these concerns were not an immediate health or safety concern to building occupants. However, due to individual sensitivities and predisposing health factors, it is possible that some building occupants may elicit a health response to agents and / or conditions identified during the evaluation. Therefore, to further improve IAQ, prevent development of future IAQ-related problems, and to reduce the potential for IAQ-related complaints by building occupants, the IAQ Assessment Team recommends appropriate follow up of each item identified and listed in the attached evaluation.

Should any questions arise, or if the current concerns continue after the attached recommendations have been addressed, please feel free to contact me at 754-321-1638.

cc: Dr. Verda Farrow, Area Superintendent Jan Beal, Area Director Jeffrey S. Moquin, Director, Risk Management

Gerry Usallan, Project Manager, Facilities and Construction Management

Ralph Eckhardt, Broward Teachers Union

Mark Dorsett, Manager 1, Physical Plant Operations Division, Zone 1

Roy Norton, Manager Custodial/Grounds, Physical Plant Operations Division

RK/tc Enc.

Time of Day	12:30 pn	1			Evalu	uation Date Decer	nber 11, 2006
Outdoor Conditions Temperature 79.3 Relative Humidity 57.2 Ambient CO2 468							
Fish	Temperature	Range	Relative Humidity	Range (CO2	Range	# Occupants
P-1214C	70.3	72 - 78	57.8	30% - 60%	3575	Max 700 > Ambi	ent 28
Noticeable Odor No		Visible water Visible microbial damage / staining? growth?		oial Am	Amount of material affected		
Ceiling Type	Ceiling Type Homasote		No			None	
Wall Type	Paneling		No			None	
Flooring	12 x 1	2 Vinyl	No	No		None	
	Clear	Minor / Deb		ı	Corrective	Action Required	
Ceiling	Yes	No	No				
Walls	Yes	No	No				
Flooring	Yes	No	No				
HVAC Supply	Grills No	Ye	Yes	Cle	ean with W	excide disinfectan	t
HVAC Return	Grills No	Ye	Yes	Cle	ean with W	excide disinfectan	t
Ceiling at Sup Grills	ply No	Ye	Yes		Clean a	s appropriate	
Surfaces in Ro	oom No	Yes	Yes		Clean a	s appropriate	

IAQ Assessment

Cypress Bay High School

3623

December 11, 2006

Location Number
Evaluation Requested

Observations

Findings:

- Dust and debris on HVAC supply and return grills
- Dust and debris on ceiling at HVAC supply grills
- Minor dust on elevated surfaces
- CO2 level was elevated at the time of the assessment
- Wood under the VCT is wet due to water evaporating under the portable

Recommendations:

Site Based Maintenance:

- Clean HVAC supply and return grills with Wexcide disinfectant solution
- Clean ceiling at HVAC supply grills
- Clean elevated surfaces
- Continue to monitor this location for any signs of microbial growth as well as dust and debris accumulation and clean as appropriate

Physical Plant Operations:

- Evaluate A/C unit for proper operation and repair as appropriate to lower CO2 level. Appears that fresh air intake may be restricted or closed.
- Evaluate cause of wet VCT. There has been a continuing issue with water evaporating under the portables at this site.