

RISK MANAGEMENT...

managing risk with responsibility

Jeffrey S. Moquin, Director
Risk Management Department

Telephone: 754-321-3200
Facsimile: 754-321-3290

July 15, 2008

Signature on File

TO: Mr. Frank Zagari, Principal
Indian Ridge Middle School

FROM: Robert Krickovich, Coordinator, LEA
Facilities and Construction Management

SUBJECT: Indoor Air Quality (IAQ) Assessment
FISH 218 and 218A

<u>For Custodial Supervisor Use Only</u>	
<input type="checkbox"/>	Custodial Issues Addressed
<input type="checkbox"/>	Custodial Issues Not Addressed

On July 8, 2008 I conducted an assessment FISH 218 and 218A at **Indian Ridge Middle School**. This evaluation included observations of the flooring system, ceiling tiles, false ceiling plenum, environmental surfaces, interior and exterior walls, and the accessible ventilation equipment. Additionally, environmental parameter measurements were taken to include temperature, relative humidity, and carbon dioxide. The detailed findings, along with the recommended corrective action can be found on the attached IAQ Assessment Worksheets.

Generally, the IAQ Assessment did not identify any existing conditions significantly impacting IAQ and thereby presenting immediate health and safety concerns to building occupants. However, due to individual sensitivities and predisposing health factors, it is possible that some building occupants may elicit a health response to agents and / or conditions identified during the evaluation. Therefore, to further improve IAQ, prevent development of future IAQ-related problems, and to reduce the potential for IAQ-related complaints by building occupants, the IAQ Assessment Team recommends appropriate follow up of each item identified and listed in the attached evaluation.

Please ensure that your Head Facilities Serviceperson receives a copy of this correspondence so that the recommendations requiring their attention can be addressed. Within two weeks a representative from the Custodial/Grounds Department will conduct a follow-up visit to ensure that all issues have been appropriately addressed.

Should any questions arise, or if the current concerns continue after the attached recommendations have been addressed, please feel free to contact me at 754-321-1638.

cc: Dr. Verda Farrow, Area Superintendent
Jan Beal, Area Director
Jeffrey S. Moquin, Director, Risk Management
James Carballo, Project Manager, Facilities and Construction Management
Ralph Eckhardt, Broward Teachers Union
Roy Jarrett, Federation of Public Employees
Mark Dorsett, Manager 1, Physical Plant Operations Division, Zone 1
Roy Norton, Manager Custodial/Grounds, Physical Plant Operations Division

RK/tc
Enc.

IAQ Assessment

Location Number
 Evaluation Requested
 Evaluation Date

Indian Ridge Middle School

Time of Day

Outdoor Conditions Temperature Relative Humidity Ambient CO2

Fish	Temperature	Range	Relative Humidity	Range	CO2	Range	# Occupants
<input type="text" value="218"/>	<input type="text" value="71"/>	<input type="text" value="72 - 78"/>	<input type="text" value="65.4"/>	<input type="text" value="30% - 60%"/>	<input type="text" value="522"/>	<input type="text" value="Max 700 > Ambient"/>	<input type="text" value="3"/>
Noticeable Odor		Visible water damage / staining?		Visible microbial growth?		Amount of material affected	
<input type="text" value="No"/>		<input type="text" value="No"/>		<input type="text" value="No"/>		<input type="text" value="None"/>	
Ceiling Type	<input type="text" value="2 x 4 Lay In"/>		<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text" value="None"/>		
Wall Type	<input type="text" value="Drywall"/>		<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text" value="None"/>		
Flooring	<input type="text" value="12 x 12 Vinyl"/>		<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text" value="None"/>		

	Clean	Minor Dust / Debris	Needs Cleaning	Corrective Action Required
Ceiling	<input type="text" value="Yes"/>	<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text"/>
Walls	<input type="text" value="Yes"/>	<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text"/>
Flooring	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean and sanitize"/>
HVAC Supply Grills	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean with Wexcide disinfectant"/>
HVAC Return Grills	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean with Wexcide disinfectant"/>
Ceiling at Supply Grills	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean as appropriate"/>
Surfaces in Room	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean as appropriate"/>

Observations

Findings:

- Floors were being stripped and cleaned at the time of the assessment resulting in elevated humidity level.
- Heavy dust build up on floor in corners, around base of walls, and between walls and furnishings
- Dust and debris on HVAC supply and return grills
- Dust build up on ceiling at HVAC supply grills
- Dust build up on environmental surfaces throughout the room

Recommendations:

Site Based Maintenance:

- Thoroughly clean and sanitize floor concentrating in corners, around base of walls and between walls and furnishings
- Clean HVAC supply and return grills with Wexcide disinfectant solution
- Clean ceiling at HVAC supply grills
- Thoroughly clean all surfaces throughout the room
- Continue to monitor this location for any signs of microbial growth as well as dust and debris accumulation and clean as appropriate

IAQ Assessment

Location Number
 Evaluation Requested
 Evaluation Date

Indian Ridge Middle School

Time of Day

Outdoor Conditions Temperature Relative Humidity Ambient CO2

Fish	Temperature	Range	Relative Humidity	Range	CO2	Range	# Occupants
<input type="text" value="218A"/>	<input type="text" value="70.9"/>	<input type="text" value="72 - 78"/>	<input type="text" value="58.3"/>	<input type="text" value="30% - 60%"/>	<input type="text" value="542"/>	<input type="text" value="Max 700 > Ambient"/>	<input type="text" value="1"/>
Noticeable Odor		Visible water damage / staining?		Visible microbial growth?		Amount of material affected	
<input type="text" value="No"/>		<input type="text" value="No"/>		<input type="text" value="No"/>		<input type="text" value="None"/>	
Ceiling Type	<input type="text" value="2 x 4 Lay In"/>		<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text" value="None"/>		
Wall Type	<input type="text" value="Drywall"/>		<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text" value="None"/>		
Flooring	<input type="text" value="12 x 12 Vinyl"/>		<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text" value="None"/>		

	Clean	Minor Dust / Debris	Needs Cleaning	Corrective Action Required
Ceiling	<input type="text" value="Yes"/>	<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text"/>
Walls	<input type="text" value="Yes"/>	<input type="text" value="No"/>	<input type="text" value="No"/>	<input type="text"/>
Flooring	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean and sanitize"/>
HVAC Supply Grills	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean with Wexcide disinfectant"/>
HVAC Return Grills	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean with Wexcide disinfectant"/>
Ceiling at Supply Grills	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean as appropriate"/>
Surfaces in Room	<input type="text" value="No"/>	<input type="text" value="Yes"/>	<input type="text" value="Yes"/>	<input type="text" value="Clean as appropriate"/>

Observations

Findings:

- Heavy dust build up on floor in corners, around base of walls, and between walls and furnishings
- Dust and debris on HVAC supply and return grills
- Dust build up on ceiling at HVAC supply grills
- Dust build up on environmental surfaces throughout the room

Recommendations:

Site Based Maintenance:

- Thoroughly clean and sanitize floor concentrating in corners, around base of walls and between walls and furnishings
- Clean HVAC supply and return grills with Wexcide disinfectant solution
- Clean ceiling at HVAC supply grills
- Thoroughly clean all surfaces throughout the room
- Continue to monitor this location for any signs of microbial growth as well as dust and debris accumulation and clean as appropriate